

THE SINDHU RESETTLEMENT CORPORATION LIMITED
(FOUNDER AND BUILDERS OF GANDHIDHAM & ADIPUR TOWNSHIP)



CIN # U45300GJ1948PLC001115

Plot No. 4 & 5, DC - 3, Rampath Road, Adipur(Kutch)

Regd. Office : Adipur (Kutch) 370205

E-Mail : src@sindhu-src.org. / Website : www.sindhu-src.org (Phone :02836 260404)

QUOTATION

**Name of Work : Repairing & Maintenance work in Library Building/Bhai Pratap Samadhi
in Ward-2A at Adipur**

Sr. No.	Item Discription	Qty	Unit	Rate	Amount
1	Removing colour wash by scrapping & sand papering & preparing the surface smooth including necessary repairs & scracthes/cracks etc/ complete as directed by Engineer in charge	200	M2		
2	18 mm thick cement plaster in two coats under layer 12 mm cement plaster 1:5 (1 cement : 5 screened coarse sand) finished with a top layer 6mm thick cement plaster 1:6 (1 cement : 6 screened fine sand) including all labour & material, curing(7 days minimum) complete as directed by Engineer incharge	200	M2		
3	Repairs to plaster of thickness 12 mm to 20 mm with cement mortar 1:4(1 cement : 4 screened fine sand) in patches of area 2.5 sq.meters and under including cutting the patch in proper shape, racking out joints and preparing and palstering the surface of the walls, all labour and material, curing(7 days minimum) complete, including disposal of rubbish , all complete as per directions of Engineer-in-charge	500	M2		

Sr. No.	Item Discription	Qty	Unit	Rate	Amount
4	Making pedestal for electric pole by constructing brick masonry in CM 1:6 (1 Cement : 6 screened coarse sand) including removing existing damaged pedestal, plastering the same in CM 1:4 (1 cement : 6 screened fine sand), curing(7 days minimum) etc. complete as per directions of Engineer incharge	12	EACH		

Dated signature of Contractor

Sr. Ex. Engineer

SPECIAL TERMS & CONDITIONS OF THE WORK WILL BE AS UNDER:-

- 1** The location of work is Library building/ Bhai Pratap Samadhi in Ward-2A at Adipur (Kutch).
- 2** The contractor should visit the site before tendering & no claim whatsoever will be accepted for same later.
- 3** 5% Security deposit will be deducted from the bills which will be refunded after six months of satisfactory completion of work .
- 4** The work is to be carried out as per specifications laid down in CPWD, item descriptions & as per instruction of Engineer incharge.
- 5** The work is to be completed within Sixty days period.
- 6** The deduction of Income Tax will be made as per Income Tax Act.
- 7** Rates shall be inclusive of all taxes including GST.
- 8** The Contractor has to take proper safety measures while carrying out the work to avoid any accident, if any thing happens for which Corporation will not be held responsible.
- 9** All scaffolding etc. are to be brought by contractor at his own cost.
- 10** The rates are same for all floor & levels.
- 11** The last date of submission of quotation is 2nd June'2025 up to 16.00 Hrs.
- 12** The payment will be made as per the measurements of actual work done.
- 13** The payment will be made after satisfactory completion of work.
- 14** The rates are inclusive of royalty, loading & unloading of raw materials
- 15** The contractor has to follow all the labour laws, minimum wages act & all other laws enforced.
- 16** The Corporation reserve the right to accept or reject any or all the tenders without assigning any reason.

Dated Signature of contractor

Sr. Executive Engineer
S.R.C. LTD.